

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-171-20658-00-00  
Spot: W2SENE Sec/Twnshp/Rge: 30-18S-31W  
4369 feet from S Section Line, 488 feet from E Section Line  
Lease Name: MCKEAN TRUST Well #: 1-30-1831  
County: SCOTT Total Vertical Depth: 5070 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PKWY SUITE 2  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2900		
CIBP		4370		
CIBP		4430		
DVT		2973		WITH 495 SX CMT
PROD	5.5	5070	0	WITH 325 SX CMT
SURF	8.625	347		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/07/2018 12:00 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: TY LUNN Company: STELBAR OIL Phone: (316) 264-8378

Proposed Plugging Method: PUMP 200# HULLS & 270 SX CMT DOWN 5 1/2" CASING. PRESSURE TO 500#. FILL ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/07/2018 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

FILL 5 1/2" CASING WITH CMT FROM 2791' TO 0' USING 200# HULLS & 290 SX CMT. PRESSURE TO 400#. HOLDING. ATTEMPT TO PUMP DOWN ANNULUS AT 700 PSI. COULD NOT. TOP OFF 5 1/2" CASING WITH 10 SX CMT.

Top	Bot	Thru	Comments
2783	2791	OH	


INVOICED  
JUL 18 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
JUN 18 2018  
KCC DODGE CITY



*Rms*  
Form CP-2/3