

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-025-21221-00-00  
Spot: SESWNENE Sec/Twnshp/Rge: 26-32S-25W  
1314 feet from N Section Line, 958 feet from E Section Line  
Lease Name: BIG BASIN Well #: 1  
County: CLARK Total Vertical Depth: 5630 feet

Operator License No.: 35312  
Op Name: PARWEST LAND EXPLORATION, INC.  
Address: 2601 NW EXPRESSWAY SUITE 707 WE  
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5480		WITH 2 SX CMT
COND	13.375	85		WITH 100 SX CMT
PROD	4.5	5630	1550	WITH 100 SX CMT
SURF	8.625	1028		WITH 500 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/17/2018 9:00 AM  
Plug Co. License No.: 34367 Plug Co. Name: LONESTAR SERVICES LLC  
Proposal Rcvd. from: LARRY ROMME Company: LONESTAR SERVICES LLC Phone: (620) 626-7100

Proposed Plugging Method: CIBP @ 5480' WITH 2 SX CMT. PLUG AT 1075' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/17/2018 10:40 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5480' WITH 2 SX CMT. 1ST PLUG AT 1087' WITH 50 SX CMT. 2ND PLUG AT 298' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED & THE HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5532	5550		

INVOICED  
JUL 13 2018


Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT

Plugged through: TBG

District: 01

RECEIVED  
MAY 22 2018  
KCC DODGE CITY

Signed



(TECHNICIAN)