

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-20459-00-01
Spot: NWSWSESW Sec/Twnshp/Rge: 27-14S-18W
349 feet from S Section Line, 3814 feet from E Section Line
Lease Name: ENGEL Well #: 1-V
County: ELLIS Total Vertical Depth: 3661 feet

Operator License No.: 32016
Op Name: PIONEER RESOURCES INC.
Address: 80 WINDMILL DR.
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	3.5	3569		265 SX CMT
PROD	5.5	3652		125 SX
SURF	8.625	283		175 SX
T1	4.5	0		Unknown depth and cement

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/24/2018 12:00 PM
Plug Co. License No.: 34266 Plug Co. Name: PRAIRIE HAWK WELL SERVICE LLC
Proposal Rcvd. from: BUTCH DREILING Company: PIONEER RESOURCES INC. DBA Phone: (785) 650-4404

Proposed Plugging Method: Ordered 270 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3620' - 3623' ARB OH.
Lower casing leaks.
Operator planned to run 3 1/2" liner but found liner in well.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/24/2018 5:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Gemini Wireline perforated at 1650' - 1266' and 660'. Prairie Hawk Well Service ran in hole with tubing to 3400'. Global rigged to tubing and pumped 90 sx cement w/250 # hulls mixed in. Pulled tubing to 1639' and pumped 50 sx cement w/50 # hulls. Pressured to 1200 psi. Pulled tubing to 1323' and pumped 20 sx cement. The cement started to push the tubing out. Pulled tubing to 535' and pumped 25 sx cement to circulate cement up 3 1/2" casing. Pulled tubing. Rigged to 3 1/2" casing and pumped 10 sx cement to pressure with 200 psi. Shut in pressure 300 psi. Rigged to 8 5/8" surface casing and pumped 5 sx cement w/300 psi. Shut in pressure 300 psi. Rigged to 4 1/2" liner and pumped 2 sx cement with 300 psi. Shut in pressure 300 psi.

GPS: 38.79951 -099.31299

Perfs:

Top	Bot	Thru	Comments
3652	3656		

INVOICED

JUL 18 2018

Remarks: GLOBAL CEMENTING CO. TICKET # 3276

Plugged through: TBG

District: 04

Signed _____

KCC WICHITA,

(TECHNICIAN)

CM

APR 27 2018

MAY 17 2018

RECEIVED