

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22915-00-00
Spot: NENW Sec/Twnshp/Rge: 27-32S-10W
4650 feet from S Section Line, 3372 feet from E Section Line
Lease Name: TRANHAM Well #: 2
County: BARBER Total Vertical Depth: 4530 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4320		WITH 2 SX CMT
PROD	5.5	4528	2802	WITH 125 SX CMT
SURF	8.625	224		WITH 200 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/28/2018 10:00 AM
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.
Proposal Revd. from: DUSTIN NEWBERRY Company: R&B OIL & GAS Phone: (620) 254-7251

Proposed Plugging Method: CIBP @ 4320' WITH 2 SX CMT. PLUG AT 640' WITH 12 SX GEL & 50 SX CMT. PLUG AT 240' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2018 12:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4320' WITH 2 SX CMT ON TOP. 1ST PLUG AT 629' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 258' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT TO FILL HOLE TO SURFACE. HOLE REMAINING FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4390	4420		
4376	4420		


INVOICED
JUL 18 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUL - 2 2018
KCC DODGE CITY

Form CP-2/3

KMS