

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-23181-00-00  
Spot: NWSWNE5W Sec/Twnshp/Rge: 34-29S-5E  
1797 feet from S Section Line, 3860 feet from E Section Line  
Lease Name: TAYLOR Well #: 1  
County: BUTLER Total Vertical Depth: 2880 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 9412 E. CENTRAL PO BOX 781775  
WICHITA, KS 67278

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP   | 4.5   | 2750       |             |          |
| PROD   | 4.5   | 2875       | 75 SX       |          |
| SURF   | 8.625 | 223        | 85 SX       |          |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/29/2018 12:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: ALAN NATION Company: \_\_\_\_\_ Phone: (620) 222-4304

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 2750 W/2 SXS AND CIRCUALTE 300'-0'.

Plugging Proposal Received By: B. J. HOPE WitnessType: NONE  
Date/Time Plugging Completed: 06/06/2018 1:45 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2750', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. LOADED CASING & PRESSURED @ 150#, HELD OK. RIH ON WIRELINE, PEEFORATED SQUEEZE HOLES 300'-301' (4 HOLES). COPELAND ACID SWEDGED INTO 4 1/2" CASING, ESTABLISHED CIRCULATION, MIXED & PUMPED 135 SXS 60/40 POZMIX 4% GEL, CC & 150# HULLS TO SURFACE. CEMENT CIRCULATED. 6-6-2018 TAGGED CEMENT @ 215', RIH WITH TUBING ON INSIDE @ 215', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL TO SURFACE. RIH W/1" TUBING ON BACKSIDE @ 135'. COPELAND MIXED & PUMPED 10 SXS 60/40 4% GEL TO SURFACE. PA COMPLETE ON 6-6-2018.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2801 | 2808 |      |          |

INVOICED  
JUL 18 2018

Remarks: TICKET #46401 & 47645.

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

JK