

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24164-00-00
Spot: SWNESE Sec/Twnshp/Rge: 7-33S-6E
2029 feet from S Section Line, 567 feet from E Section Line
Lease Name: CHASE Well #: 5
County: COWLEY Total Vertical Depth: 3141 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP | 5.5 | 3000 | | |
| PROD | 5.5 | 3140 | | 100 SX |
| SURF | 8.625 | 320 | | 200 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/29/2018 10:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: ALAN NATION Company: _____ Phone: (620) 222-4304

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 3000' WITH 2 SKS. CIRCULATE 370'-0'.

Plugging Proposal Received By: B. J. HOPE WitnessType: NONE
Date/Time Plugging Completed: 05/29/2018 11:50 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3,000', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. LOADED CASING & PRESSURED @ 150#, HELD OK. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 370' - 371' (4 HOLES). COPELAND ACID SWEDGED INTO 5.5" CASING, ESTABLISHED CIRCULATION, MIXED & PUMPED 135 SXS 60/40 POZMIX 4% GEL 4% CC & 150# HULLS TO SURFACE. CEMENT CIRCUALTED. TICKET #47644. 6-6-2018, TAGGED CEMENT @ 65', RIH WITH TUBING @ 65', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 20 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. TICKET #46402.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3090 | 3100 | | |

INVOICED
JUL 18 2018

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

✓ SK