

TO: STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-035-23679-00-00  
 Spot: NWSENW Sec/Twnshp/Rge: 16-34S-3E  
3680 feet from S Section Line, 3652 feet from E Section Line  
 Lease Name: JIMMERSON Well #: 2  
 County: COWLEY Total Vertical Depth: 3374 feet

Operator License No.: 5120  
 Op Name: RANGE OIL COMPANY, INC.  
 Address: 9412 E. CENTRAL PO BOX 781775  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2850		
CIBP	4.5	3240		
PROD	4.5	3373		150 SX
SURF	8.625	330		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/29/2018 8:00 AM  
 Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
 Proposal Rcvd. from: ALAN NATION Company: \_\_\_\_\_ Phone: (620) 222-4304

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 2850 W/2 SXS, 3240 W/ 2 SXS. CIRCUALTE 380'-0'.

Plugging Proposal Received By: B. J. HOPE Witness Type: NONE  
 Date/Time Plugging Completed: 06/06/2018 10:35 AM KCC Agent: DUANE KRUEGER

**Actual Plugging Report:**

RIH ON WIRELINE SET CIBP @ 3240' W/2 SXS CEMENT ON TOP. RIH ON WIRELINE SET CIBP @ 2850' W/2 SX CEMENT ON TOP. PRESSURED @ 150# HELD OK. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 380'-381' (4 HOLES). COPELAND ACID SWEDGED INTO 4.5" CASING, ESTABLISHED CIRCULATION, MIXED & PUMPED 145 SXS 60/40 POZMIX 4% GEL & 150# HULLS TO SURFACE. CEMENT CIRCULATED. TICKET #47643. 6-6-2018, TAGGED CEMENT @ 60'. DUMPED 20 SXS 60/40 POXMIX 4% GEL TO SURFACE. TOPPED WELL BACK TO SURFACE. TICKET #46403.

**Perfs:**

Top	Bot	Thru	Comments
3291	3297		
2920	2937		

INVOICED

JUL 13 2018

Remarks:

Plugged through: TBG

District: 02

Signed

*Duane Krueger*

(TECHNICIAN)

*JK*