

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-22133-00-02
Spot: N2NENE Sec/Twnshp/Rge: I6-25S-12W
494 feet from S Section Line, 661 feet from E Section Line
Lease Name: DESELMS Well #: 1-OWWO
County: STAFFORD Total Vertical Depth: 4210 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3900		WITH 2 SX CMT
PROD	5.5	4073	1600	WITH 80 SX CMT
SURF	8.625	293		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/29/2018 9:00 AM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: CIBP @ 3900' WITH 2 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2018 10:00 AM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3900' WITH 2 SX CMT ON TOP. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 35 SX CMT. HOLE STAYING FULL.

Perfs:

Top	Bot	Thru	Comments
3950	3970		

INVOICED
JUL 18 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed *Ken Scofield*

(TECHNICIAN)

RECEIVED
JUL - 2 2018
KCC DODGE CITY

Form CP-2/3

KMS