

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-31603-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 30-31S-14E
2291 feet from S Section Line, 2171 feet from E Section Line
Lease Name: FALER Well #: 10-30
County: MONTGOMERY Total Vertical Depth: 1468 feet

Operator License No.: 35497
Op Name: REDBUD OIL & GAS OPERATING, LLC
Address: 16000 STUEBNER AIRLINE RD SUITE 3
SPRING, TX 77379

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1459		200 SX
SURF	8.65	22		8 SX
T1	2.375	1208		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 03/29/2018 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: MIKE TAYLOR Company: _____ Phone: (620) 627-2499

Proposed Plugging Method: Cement to Surface

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2018 12:00 PM KCC Agent: DUANE SIMS


Actual Plugging Report: _____ Perfs: _____

Ran 1" to 1452' gelled hole and spotted 5 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 34 sacks of cement with 4% gel were used to plug this well.

RECEIVED
KCC DIST # 3
MAY 22 2018
CHANUTE, KS

DS
INVOICED
JUL 18 2018

Remarks: WELL PLUGGED DUE TO DENIED CP-111. PAST 10 SHUT IN DATE.
Plugged through: TBG

District: 03 Signed 
(TECHNICIAN)