

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21541-00-00
Spot: NESWSESW Sec/Twnshp/Rge: 25-11S-33W
653 feet from S Section Line, 1913 feet from W Section Line
Lease Name: MICHAELIS Well #: 25-1
County: LOGAN Total Vertical Depth: 4630 feet

Operator License No.: 34099
Op Name: RICHLAND OIL INVESTMENTS, LLC
Address: 608 E. 1ST PO BOX 166
PALCO, KS 67657

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	226		165 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/19/2018 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: BILL Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-0706

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY WitnessType: NONE
Date/Time Plugging Completed: 04/19/2018 4:30 PM KCC Agent: CHRIS NEELEY

Actual Plugging Report:

1st plug @2590 w/50 sx
2nd plug @1580 w/100 sx
3rd plug @280 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:


INVOICED
JUL 18 2018

Remarks: GLOBAL

Plugged through: DP

District: 04

Signed



KCC WICHITA

(TECHNICIAN)

CM

MAY 1 2018

MAY 17 2018

Form CP-2/3

MAY 0 1 2018

RECEIVED