

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-22078-00-00
Spot: NWSWSENE Sec/Twnshp/Rge: 18-13S-31W
2140 feet from N Section Line, 1100 feet from E Section Line
Lease Name: WRAY 18A Well #: 1
County: GOVE Total Vertical Depth: 4720 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>4767</u>	PROD	4.5	4706		225 SX
Op Name: <u>RITCHIE EXPLORATION, INC.</u>	SURF	8.625	218		175 SX
Address: <u>8100 E 22ND ST N # 700 BOX 783188</u> <u>WICHITA, KS 67278</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/26/2018 10:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. DBA Phone: (785) 216-0155

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
8 5/8" surface casing set at 218' w/175 sx cement.
4 1/2" production casing set at 4706' w/225 sx cement.
Stage collar set at 2403' w/450 sx cement. Cement did not circulate. Alt II exception approved.
TD 4720', PBSD 4666'.
Perforations: 4151' - 4155' LKC and 4546' - 4550' Johnson.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/26/2018 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4100' and pumped 100 sx cement w/400 # hulls. Pulled tubing to 3050' and pumped 100 sx cement. Pulled tubing to 1552' and pumped 110 sx cement. Circulated cement to surface. Pulled tubing to surface. Connected to 4 12" casing and pumped 10 sx cement. Connected to 8 5/8" surface casing and pumped 15 sx cement. Shut in pressure 400 psi.

GPS: 38.92567N -100.80145W

Perfs:

Top	Bot	Thru	Comments
4547	4550		
4546	4550		
4152	4155		
4151	4155		

INVOICED
JUL 18 2018

Remarks: EXPRESS WELL SERVICE PULLING UNIT AND GLOBAL OILFIELD SERVICES TICKET # 3326
Plugged through: TBG

District: 04 Signed Darrel Dipman (TECHNICIAN) *CM*

KCC WICHITA
MAY 17 2018
RECEIVED

MAY 01 2018