

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-27646-00-00
Spot: NWNENWSW Sec/Twnshp/Rge: 14-28S-18E
2425 feet from S Section Line, 985 feet from W Section Line
Lease Name: BAILEY, MARION L Well #: 14-13
County: NEOSHO Total Vertical Depth: 957 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	954		125 SX
SURF	8.625	20		5 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2018 9:30 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDON JAMISON Company: RIVER ROCK OPERATING Phone: (620)432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 06/06/2018 9:30 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to 930 ft inside the 5.5 inch production pipe. The well was pumped full of cement from btm to top thru the cement string. The cement string was pulled to 200 ft and the well again pumped full. The cement string was removed and the well topped off with cement. According to operator, 126 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
804	812		

RECEIVED
KCC DIST # 3
JUN 29 2018
CHANUTE, KS
AD
INVOICED
JUL 18 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)