

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-133-27645-00-00  
Spot: NESENWSW Sec/Twnshp/Rge: 14-28S-18E  
1705 feet from S Section Line, 1080 feet from W Section Line  
Lease Name: BAILEY, MARION L Well #: 14-14  
County: NEOSHO Total Vertical Depth: 957 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 5.5   | 954        |             | 125 SX   |
| SURF   | 8.625 | 20         |             | 5 SX     |
| TI     | 2.375 | 883        |             |          |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/06/2018 11:30 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 06/06/2018 11:30 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to 920 ft inside the 5.5 inch production pipe. The well was pumped full of cement from btm to top thru the cement string. The cement string was pulled to 200 ft and the well again pumped full. The cement string was removed and the well topped off with cement. According to operator, 119 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 803 | 812 |      |          |

RECEIVED  
KCC DIST # 3  
JUN 29 2018  
CHANUTE, KS

INVOICED *AD*

JUL 18 2018

Remarks:

Plugged through: CSG

District: 03

Signed

*Alan M. Dunning*  
(TECHNICIAN)