

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-20527-00-00
Spot: NESENESE Sec/Twnshp/Rge: 33-27S-19E
1859 feet from S Section Line, 312 feet from E Section Line
Lease Name: LA RUE A Well #: 1-B
County: NEOSHO Total Vertical Depth: 680 feet

Operator License No.: 32595
Op Name: MSG RESOURCES INC.
Address: 971 1400TH ST
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10	20		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/24/2018 2:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: MIKE BROWN Company: MSG RESOURCES Phone: (62) 036-5038

Proposed Plugging Method: Wash 1 inch string of pipe to bottom, circulate cement to top, pull 1 inch, and top off with cement

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 04/24/2018 2:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was lowered to 200 ft without obstruction. The well was then washed down to 648 ft and the well pumped full of cement from btm to top thru the cement string. The cement string was pulled to 250 ft and the well again pumped full. The cement string was removed and the well topped off with cement. According to operator, 189 sacks of portland cement were used to plug well.

Perfs:

RECEIVED
KCC DIST # 3
JUN 29 2018
CHANUTE, KS

INVOICED
JUL 17 2018

AD

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)