

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-135-24346-00-00
 Spot: SENEWSWSW Sec/Twnshp/Rge: 21-16S-23W
711 feet from S Section Line, 633 feet from W Section Line
 Lease Name: BUXTON Well #: 1-21
 County: NESS Total Vertical Depth: 4680 feet

Operator License No.: 5144
 Op Name: MULL DRILLING COMPANY, INC.
 Address: 1700 N WATERFRONT PKWY BLDG 120
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4115		WITH 2 SX CMT
PC	5.5	1857		WITH 180 SX CMT
PROD	5.5	4658	0	WITH 130 SX CMT
SURF	8.625	236		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2018 9:00 AM
 Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
 Proposal Rcvd. from: KYLE RANDA Company: MULL DRILLING Phone: (785) 798-0591

Proposed Plugging Method: PUMP 35 SX CMT & 150# HULLS. SPACER TO 1900' THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 06/06/2018 10:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 35 SX CMT & 150# HULLS, 43 BBL SPACER, THEN 185 SX CMT. MAXIMUM PRESSURE 1500#. SHUT IN PRESSURE 700#. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4472	4474		

INVOICED
 JUL 17 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWFIT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier
 (TECHNICIAN)

RECEIVED
 JUN 18 2018
 KCC DODGE CITY

KMS