

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25315-00-01
Spot: SWSNWSW Sec/Twnshp/Rge: 6-16S-22W
1333 feet from S Section Line, 4436 feet from E Section Line
Lease Name: KWT Well #: 1-6
County: NESS Total Vertical Depth: 4490 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 120
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4250		WITH 2 SX CMT
PC	5.5	1777		WITH 160 SX CMT
PROD	5.5	4479	0	WITH 175 SX CMT
SURF	8.625	221		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2018 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: KYLE RANDA Company: MULL DRILLING Phone: (785) 798-0591

Proposed Plugging Method: PUMP 35 SX CMT & 150# HULLS. SPACER TO 1800' THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2018 12:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 35 SX CMT & 150# HULLS, 44 BBLs SPACER THEN 175 SX CMT.
MAXIMUM PRESSURE 2000#. SHUT IN WITH 500#. TIED ONTO BACKSIDE &
PUMPED 10 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4398	4402		
4388	4402		
4300	4303		

INVOICED
JUL 17 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed

Michael Maier

(TECHNICIAN)

RECEIVED
JUN 18 2018
KCC DODGE CITY

Form CP-2/3

KMS