

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-039-21186-00-00
Spot: SWSENE Sec/Twnshp/Rge: 7-5S-30W
1210 feet from N Section Line, 550 feet from E Section Line
Lease Name: JUENEMANN Well #: 1-7
County: DECATUR Total Vertical Depth: 4600 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4598		175 SX
SURF	8.625	225		195 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/22/2018 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (800) 962-1206

Proposed Port collar at 2662' w/175 sx cwc.
Plugging Production perforations: 4049' - 4051' and 4130' - 4135'.
Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls and 1100 # gel spacer.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/22/2018 7:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3997'. Hurricane Services pumped 1100 # gel followed by 75 sx cement w/350 # hulls. Pulled tubing to 2665' and pumped 130 sx cement w/100 # hulls. Pulled tubing to 1332' and pumped 135 sx cement w/50 # hulls. Cement circulated. PTOH. Topped off 5 1/2" casing with 30sx cement. Hooked up to backside and pumped 20 sx cement. Maximum pressure 350 #. Shut in pressure 350 #.

Perfs:

Top	Bot	Thru	Comments
4130	4135		
4049	4051		

INVOICED
JUL 17 2018

Remarks: HURRICANE SERVICES TICKET # 100928

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 29 2018

JUN 12 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3