

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-20910-00-00
Spot: SESWNWSE Sec/Twnshp/Rge: 22-2S-36W
1550 feet from S Section Line, 2210 feet from E Section Line
Lease Name: PTL Well #: 1-22
County: RAWLINS Total Vertical Depth: 5060 feet

Operator License No.: 30606

String Size Depth (ft) Pulled (ft) Comments

Op Name: MURFIN DRILLING CO., INC.

PROD 5.5 5053 175 SX

Address: 250 N WATER STE 300
WICHITA, KS 67202

SURF 8.625 392 350 sx

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/02/2018 9:45 AM

Plug Co. License No.: 34059

Plug Co. Name: HURRICANE SERVICES, INC.

Proposal Rcvd. from: JOHN TURNER

Company: MURFIN DRILLING CO., INC. DBA Phone: (785) 443-1031

Proposed Plugging Method: Ordered 480 sx 60/40 pozmix 4% gel cement, 500 # gel and 800 # hulls.

8 5/8" surface casing set at 392' w/350 sx cement.

5 1/2" production casing set at 5053' w/175 sx cement. TOC at 3450'.

No stage collar set. Dakota exempt area.

TD 5060'. PBT 5031'.

Perforations: LKC 4265' - 4269', 4328' - 4332' and 4337' - 4341'.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 05/02/2018 1:00 PM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

Perforated production casing at 3238' and 2534'. Ran tubing to 4085' and pumped 500 # gel followed by 70 sx cement w/350 # hulls. Pulled tubing to 3242' and pumped 155 sx cement w/200 # hulls. Pulled tubing to 1653' and pumped 180 sx cement w/200 # hulls. Circulated cement to surface. Pulled tubing to surface. Connected to 8 5/8" surface casing and pumped 60 sx cement. Pressured to 280 #. Connected to 5 1/2" production casing and pumped 20 sx cement.

Top	Bot	Thru	Comments
4337	4341		
4328	4332		
4265	4269		

GPS: 39.86226N -101.34303W

INVOICED

JUL 17 2018

Remarks: HURRICANE SERVICES INC. PULLING UNIT AND PUMPT TRUCK. HURRICANE CEMENT TICKET # 100913

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

C.M.

KCC WICHITA

MAY 17 2018

RECEIVED

MAY 13 2018