

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-01745-00-00
Spot: S2N2SW Sec/Twnshp/Rge: 27-9S-20W
1650 feet from S Section Line, 1320 feet from W Section Line
Lease Name: HINKHOUSE Well #: 13
County: ROOKS Total Vertical Depth: 3818 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN LLC
Address: 15 E 5TH ST STE 3300
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3616		125 SX
SURF	8.625	120		110 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/13/2018 9:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: DUANE WOOD Company: NADEL AND GUSSMAN LLC DBA Phone: (785) 737-3051

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Tubing stuck in hole at 2594'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/13/2018 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Perforated 5 1/2" casing at 1800', 1100' and 118'. Ran tubing to 2590' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2090' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 1100' and pumped 120 sx cement w/100 # hulls to circulate cement to surface. Closed off 5 1/2" casing and pumped 60 sx cement to circulate 8 5/8" x 5 1/2" annulus to surface. Pulled tubing. Topped off 5 1/2" casing and 8 5/8" x 5 1/2" annulus w/60 sx cement.

GPS: 39.23913N -099.54477W

INVOICED

JUL 17 2018

Remarks: COPELAND ACID AND CEMENT TICKET # 45870

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

JUN 18 2018

JUN 25 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3