

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-081-22049-00-00  
Spot: NENENWSW Sec/Twnshp/Rge: 25-27S-32W  
2498 feet from S Section Line, 4102 feet from E Section Line  
Lease Name: BLACK Well #: 1  
County: HASKELL Total Vertical Depth: 2768 feet

Operator License No.: 9412  
Op Name: NIGHTENGALE, HENRY (DECEASED)  
Address: 694 ROAD SS  
SUBLETTE, KS 67877

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2767	0	WITH 300 SX CMT
SURF	8.625	993		WITH 370 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/02/2018 10:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: KURT OSTEBUHR Company: HENRY NIGHTENGALE Phone: (620) 276-3442

Proposed Plugging Method: DETERMINE TOC WITH CBL. IF CMT IS ABOVE 500' SWAB CASING DOWN TO 2100' THEN FILL TO SURFACE SLOWLY ALLOWING THE AIR TO WORK OUT. THEN FILL THE ANNULUS WITH CMT. IF TOC IS BETWEEN 500'-993' PERF ABOVE THE TOC THEN RUN TBG TO 2100' & CIRCULATE CMT TO SURFACE. IF TOC IS BELOW 993' PERF 4 HOLES AT 1000' THEN RUN TBG TO 2100' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/02/2018 12:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

WELL WAS NEVER PERFORATED. RAN CBL & SHOWED TOC @ 80'. SWABBED CASING DOWN TO 2100'. TIED ONTO CASING & PUMPED 200 SX CMT TO SURFACE. TIED ONTO 5 1/2" X 8 5/8" ANNULUS & PUMPED 10 SX CMT TO 300 PSI.

INVOICED  
JUL 17 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: CSG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
JUL - 5 2018  
KCC DODGE CITY [Signature]