

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-20858-00-00
Spot: NESWSWSE Sec/Twnshp/Rge: 35-9S-35W
335 feet from S Section Line, 2058 feet from E Section Line
Lease Name: BARRETT FAMILY TRUST Well #: 1-35
County: THOMAS Total Vertical Depth: 4978 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 88 INVERNESS CIR E. UNIT F104
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4975		145 SX
SURF	8.625	289		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/30/2018 8:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: BRADY PFEIFFER Company: NORSTAR PETROLEUM, INC. DBA Phone: (303) 925-0696

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 1000 # gel and 500 # hulls.
8 5/8" surface casing set at 289' w/185 sx cement.
5 1/2" production casing set at 4975' w/145 sx cement.
Port Collar set at 2854' w/325 sx Multi-Density cement. Cement did not circulate. TOC near 1200'. Dakota: 1583' - 1883'.
TD 4978' and PBTD 4468'.
Perforations: 4449' - 4458', 4483' - 4487' are shut off with CIBP set at 4468'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/30/2018 12:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4400' and pumped 1000 # gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 2850' and pumped 140 sx cement w/100 # hulls. Pulled tubing to 1425' and pumped 145 sx cement w/50 # hulls. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 20 sx cement. Connected to 8 5/8" surface casing and pumped 25 sx cement. Pressured to 300 #.

GPS: 39.22239N -101.19373W

Perfs:

Top	Bot	Thru	Comments
4483	4487		
4449	4458		

INVOICED

JUL 17 2018

Remarks: CHEYENNE WELL SERVICE PULLING UNIT AND QES PRESSURE PUMPING LLC. TICKET # 55,144

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

cm

KCC WICHITA

MAY 17 2018

RECEIVED

MAY 03 2018

Form CP-2/3