

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-20910-00-00
Spot: NWSWNWSE Sec/Twnshp/Rge: 33-9S-35W
1828 feet from S Section Line, 2347 feet from E Section Line
Lease Name: HAG-HOFF Well #: 1-33
County: THOMAS Total Vertical Depth: 4950 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 88 INVERNESS CIR E. UNIT F104
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4949		175 SX
SURF	8.625	307		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2018 10:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: BRADY PFEIFFER Company: NORSTAR PETROLEUM, INC. DBA Phone: (303) 925-0696

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 900 # gel and 500 # hulls.
8 5/8" surface pipe set at 307' w/200 sx cement.
5 1/2" production casing set at 4949' w/175 sx cement.
Port Collar set at 2872' w/325 sx cement.
TD 4950'.
Perforations: squeezed off: 4358' - 4359', 4358' - 4386', 4396' - 4400', 4446' - 4452'.
Open perforations: 4427' - 4432' and 4474' - 4486'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2018 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4400' and pumped 900 # gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 2870' and pumped 140 sx cement w/100 # hulls. Pulled tubing to 1435' and pumped 150 sx cement w/50 # hulls. Circulated cement to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 20 sx cement. Connected to 8 5/8" surface casing and pumped 30 sx cement.

GPS: 39.22688N -101.23199W

Perfs:

Top	Bot	Thru	Comments
4474	4486		
4427	4432		

INVOICED
JUL 17 2018

Remarks: CHEYENNE WELL SERVICE PULLING UNIT. QES PRESSURE PUMPING LLC CEMENT TICKET # 55,159

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

MAY 22 2018

Received
KANSAS CORPORATION COMMISSION

JUN 12 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3