

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-21647-00-00  
Spot: NWNWNWSE Sec/Twushp/Rge: 4-22S-23W  
2466 feet from S Section Line, 2408 feet from E Section Line  
Lease Name: BRADSHAW Well #: 1-4  
County: HODGEMAN Total Vertical Depth: 4700 feet

Operator License No.: 31652  
Op Name: NORSTAR PETROLEUM, INC.  
Address: 88 INVERNESS CIR E. UNIT F104  
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1555		CEMENTED WITH 150 SX CMT. 20 SX CMT CIRCULATED TO PIT.
PROD	5.5	4699	0	WITH 150 SX CMT
SURF	8.625	248		WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/15/2018 8:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: HAL HOSS Company: NORSTAR PETROLEUM Phone: (785) 798-5051

Proposed Plugging Method: SQUEEZE PERFS WITH 25 SX CMT & 150# HULLS. PLUG AT 1590' WITH 50 SX CMT. 660' WITH CMT TO SURFACE. PRESSURE BACKSIDE TO 300# WITH CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/15/2018 12:25 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

RAN TBG TO 4526'. PUMPED 25 SX CMT WITH 150# HULLS. 1ST PLUG AT 1605' WITH 50 SX CMT. 2ND PLUG AT 674'. CIRCULATED CMT TO SURFACE WITH 65 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT. PRESSURED BACKSIDE TO 350# WITH 40 SX CMT. HOLE STAYED FULL.

INVOICED  
JUL 17 2018

Perfs:

Top	Bot	Thru	Comments
4579	4585		

Remarks: COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed  (TECHNICIAN)

RECEIVED  
MAY 25 2018  
KCC DODGE CITY 