

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40406-00-00
Spot: SENESEW Sec/Twnshp/Rge: 10-34S-12E
1709 feet from S Section Line, 2850 feet from E Section Line
Lease Name: LOWE Well #: 7
County: CHAUTAUQUA Total Vertical Depth: 945 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	760		0 SX
SURF	10.75	40		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2018 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Revd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 05/11/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 890' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 600' and 275'. Ran 1" back into 600' and spotted 20 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 155 sacks of cement with 3% gell was used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
916	932		

RECEIVED
KCC DIST # 3
JUN 06 2018
CHANUTE, KS

DS

INVOICED


JUL 17 2018

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)