

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-10088-00-00
Spot: S2N2SE Sec/Twnshp/Rge: 25-27S-11W
1664 feet from S Section Line, 1324 feet from E Section Line
Lease Name: CUNNINGHAM UNIT B Well #: 38
County: PRATT Total Vertical Depth: 3451 feet

Operator License No.: 3880
Op Name: KC RESOURCES, INC.
Address: P. O. BOX 6749
SNOWMASS VILLAGE, CO 81615

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3250		WITH 2 SX CMT
PROD	5.5	3428	0	WITH 350 SX CMT
SURF	10.75	355		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2018 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 3250' WITH 2 SX CMT. BOND LOG FROM BELOW SALT SECTION TO SURFACE. FOUND THAT WELL HAD BEEN SQUEEZED NUMEROUS TIMES FOUND CMT BELOW SALT FROM 1600' TO 1570' & ABOVE SALT 950' TO 570' & 460' TO 345'. PERFORATE 5 1/2" CASING AT 340'. PLUGGING SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2018 4:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

BOND LOG FROM BELOW SALT SECTION TO SURFACE. FOUND THAT WELL HAD BEEN SQUEEZED NUMEROUS TIMES FOUND CMT BELOW SALT FROM 1600' TO 1570' & ABOVE SALT 950' TO 570' & 460' TO 345'. PERFORATED 5 1/2" CASING AT 340'. SET CIBP @ 3250' & PUT 2 SX CMT ON TOP OF CIBP THOROUGH DUMP BAILER. 1ST PLUG SPOT 35 SX CMT AT 1550' INSIDE 5 1/2" CASING THROUGH TBG. 2ND PLUG SPOT 35 SX CMT AT 900' INSIDE 5 1/2" CASING. 3RD PLUG FILL 5 1/2" CASING FROM 400' TO SURFACE WITH 55 SX CMT. UNABLE TO PUMP THROUGH SQUEEZE PERFS AT 340'. PUMPED DOWN 5 1/2" X 10 3/4" ANNULUS WITH 35 SX CMT. PRESSURED UP TO 700#. HELD.

Perfs:

Top	Bot	Thru	Comments
3428	3451	OH	

INVOICED

JUL 17 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED COMMON CEMENT BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

RECEIVED
JUN 13 2018
KCC DODGE CITY

Signed Stephane P. Pfeifer
(TECHNICIAN)