

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-151-10105-00-03  
 Spot: W2NWSE Sec/Twnshp/Rge: 25-27S-11W  
1980 feet from S Section Line, 2310 feet from E Section Line  
 Lease Name: CUNNINGHAM B UNIT 1 Well #: 32  
 County: PRATT Total Vertical Depth: 3844 feet

Operator License No.: 3880  
 Op Name: KC RESOURCES, INC.  
 Address: P. O. BOX 6749  
SNOWMASS VILLAGE, CO 81615

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3350		WITH 2 SX CMT
L1	4.5	3842		TOP OF LINER 2637' CMT WITH 200 SX CMT
L2	5.5	2637	2436	TOP OF LINER AT SURFACE
PROD	8.625	3411		WITH 500 SX CMT
SURF	12.5	314		WITH 300 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/12/2018 9:00 AM  
 Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
 Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (785) 252-7030

Proposed Plugging Method: SET CIBP @ 3350' WITH 2 SX CMT. RECOVER 5 1/2" LINER BELOW SALT SECTION. BOND LOG 8 5/8" PRODUCTION CASING FROM BASE OF SALT SECTION TO SURFACE. REMAINING PLUG TO BE DETERMINED.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
 Date/Time Plugging Completed: 06/13/2018 11:30 AM KCC Agent: STEVE PFEIFER

**Actual Plugging Report:**

SET CIBP @ 3350' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. CUT OFF & LAID DOWN 2436' OF 5 1/2" LINER. BOND LOG FROM BASE OF SALT SECTION TO SURFACE. FOUND NO CMT BELOW BASE OF SALT SECTION, IN SALT SECTION OR JUST ABOVE SALT SECTION. FOUND GOOD CMT FROM 540' TO SURFACE. PERFORATE 8 5/8" CASING AT 1500' & 900'. 1ST PLUG AT 1550' WITH 50 SX CMT WITH 3% CC. LET CMT SET. TAG CMT AT 1460'. 2ND PLUG AT 840' WITH 35 SX CMT. 3RD PLUG AT 330' WITH 180 SX CMT. CMT DID NOT CIRCULATE. HOLE WENT ON VACUUM. LET CMT SET. SDON. 6/13/18: TAG TOC @ 587'. PULLED TBG UP TO 330'. PUMPED DOWN TBG WITH 185 SX CMT FILLING 8 5/8" CASING FROM 330' TO SURFACE.

**Perfs:**

Top	Bot	Thru	Comments
3772	3776		

INVOICED  
 JUL 17 2018

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED COMMON CEMENT BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

RECEIVED  
 JUN 13 2018  
 KCC DODGE CITY

Signed Stephen J. Pfeifer  
 (TECHNICIAN)