

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22104-00-00
Spot: N2SESENE Sec/Twnshp/Rge: 13-17S-29W
3062 feet from S Section Line, 317 feet from E Section Line
Lease Name: EATON Well #: 2
County: LANE Total Vertical Depth: 4595 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2166		CEMENTED WITH 240 SX CMT. 20 SX CMT CIRCULATED TO PIT
PROD	4.5	4594		WITH 190 SX CMT
SURF	8.625	249		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2018 11:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: MIKE KASSELMAN Company: LD DRILLING Phone: (620) 793-3051

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 2200' & CIRCULATE CMT TO SURFACE. TIE ONTO BACKSIDE & FILL WITH CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/25/2018 5:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4450' & MIXED 35 SX CMT & 150# HULLS. PULLED TBG TO 2144' & MIXED 165 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 30 SX CMT. TIED ONTO BACKSIDE & PUMPED 40 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4511	4514		
4504	4508		
4484	4488		
4478	4482		
4460	4464		

INVOICED
JUL 17 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY SCHIPPERS CEMENTING.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUN 26 2018
KCC DODGE CITY

