

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-19276-00-00
Spot: SENENW Sec/Twnshp/Rge: 28-16S-11W
feet from Section Line, feet from Section Line
Lease Name: SEYFERT Well #: 1
County: BARTON Total Vertical Depth: 3416 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 190 | | |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/04/2018 1:00 PM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Rcvd. from: MIKE KASSELMANN Company: LD DRILLING, INC. DBA Phone: (620) 793-3051

Proposed Plugging Method: Ordered 300 sx 06/40 pozmix 4% gel cement.
Well was drilled in 1947 as a D&A. It did not have any cement below the surface pipe.
L D Drilling is replugging well because of an injection well in the area.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/04/2018 6:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Drilled down to 1460'. Below salt section. Ran tubing down to 1446' and pumped 35 sx cement. Pulled tubing to 760' and pumped 50 sx cement. Pulled tubing to 250'. Circulated cement to surface on surface pipe and around surface pipe with 160 sx cement. Pulled tubing and hole stayed full.

GPS: 38.63523 -098.54582

INVOICED

JUL 17 2018

Remarks: BASIC CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

JUN 25 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3