

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23680-00-00
Spot: SESWSESE Sec/Twnshp/Rge: 29-16S-25W
299 feet from S Section Line, 977 feet from E Section Line
Lease Name: BURGESS Well #: 1-29
County: NESS Total Vertical Depth: 4590 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4587	0	WITH 375 SX CMT
SURF	8.625	217		WITH 140 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2018 2:00 PM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Revd. from: TOM LARSON Company: LARSON OPERATING Phone: (620) 653-7368

Proposed Plugging Method: RTIH TO 4400'. PLUG AT 4400' WITH 30 SX CMT & 200# HULLS. PULL TBG TO 1980' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF 5 1/2". PUMP INTO BACKSIDE.

Plugging Proposal Received By: HEITH WALSH WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2018 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4404' & MIX 30 SX CMT & 200# HULLS. PULL TBG TO 1985' & MIXED 220 SX CMT. CIRCULATED TO SURFACE THEN LOST CIRCULATION. WENT ON A VACUUM. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 300# & HELD. 6/7/18: TIED ONTO CASING & PUMPED 140 SX CMT & FILLED CASING.

Perfs:

Top	Bot	Thru	Comments
4494	4510		
4438	4444		
4415	4421		
4399	4403		

INVOICED
JUL 17 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JUN 18 2018
KCC DODGE CITY