

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-23531-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 23-11S-16W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: BOWLBY B Well #: 1  
County: ELLIS Total Vertical Depth: 3450 feet

Operator License No.: 31385  
Op Name: M G OIL INC  
Address: PO BOX 162  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3448		225 SX
SURF	8.625	933		375 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2018 12:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: CURTIS COUNTS Company: M G OIL INC DBA Phone: (785) 483-1627

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Plugging application shows 5 1/2" casing but well has 4 1/2" casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/01/2018 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500', 950' and 350'. Ran tubing to 3300' and pumped 50 sx cement. Pulled tubing to 2950' and pumped 65 sx cement. Lost circulation at the end of pumping cement. Pulled tubing to 1800' and pumped 100 sx cement with no circulation of cement. Shut down for the day.  
06/01/2018 - Tagged cement at 900'. Ran tubing to 850'. Circulated cement to surface on casing with 75 sx cement. Pulled tubing. Tied to casing and circulated cement to surface on backside with 40 sx cement.

GPS: 39.07574 -099.06200

Perfs:

Top	Bot	Thru	Comments
3254	3346		
3024	3239		

INVOICED  
JUL 17 2018

Remarks: GLOBAL CEMENTING TICKET # 3347

Plugged through: TBG

District: 04

Signed Bruce Rodie  
Received KANSAS CORPORATION COMMISSION (TECHNICIAN) CM

JUN 25 2018

JUN 05 2018

CONSERVATION DIVISION  
WICHITA, KS