

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25317-00-00
Spot: E2NWNESW Sec/Twnshp/Rge: 1-18S-15W
2310 feet from S Section Line, 1910 feet from W Section Line
Lease Name: HILDRETH Well #: 1
County: BARTON Total Vertical Depth: 3547 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3578		150 SX
SURF	8.625	449		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/24/2018 12:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 483-2169

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 14 sx gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/24/2018 8:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 1025' and 440'. Ran tubing to 3300' and pumped 14 sx gel followed by 60 sx cement w/200 # hulls. Pulled tubing to 1450' and pumped 45 sx cement w/200 # hulls. Pulled tubing to 1025' and pumped 60 sx cement. Pulled tubing to 440'. Circulated cement to surface on casing with 70 sx cement. Pulled tubing. Tied to casing and circulated cement to surface on backside with 80 sx cement.

GPS: 38.51328 -098.93427

Perfs:

Top	Bot	Thru	Comments
3477	3481		
3462	3468		
3446	3450		
3368	3372		
3313	3317		

INVOICED
JUL 17 2018

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed

Bruce Rodie

KCC WICHITA

(TECHNICIAN)

CM

MAY 17 2018

RECEIVED

Form CP-2/3

APR 27 2018