

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25344-00-00
Spot: N2SWSWSW Sec/Twnshp/Rge: 1-18S-15W
475 feet from S Section Line, 330 feet from W Section Line
Lease Name: HILDRETH Well #: 2
County: BARTON Total Vertical Depth: 3630 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3629	2006	160 SX
SURF	8.625	1029		375 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/11/2018 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 483-2169

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 500 # hulls and 1400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE
Date/Time Plugging Completed: 05/11/2018 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 2006'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 1000' and pumped 50 sx cement w/100 # hulls. Pulled casing to 700' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 90 sx cement.

GPS: 38.50831 -098.93975

Perfs:

Top	Bot	Thru	Comments
3476	3480		
3462	3467		
3383	3386		
3378	3380		
3370	3373		

INVOICED
JUL 17 2018

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

KCC WICHITA
MAY 31 2018
RECEIVED

MAY 16 2018