

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25309-00-00
Spot: NESWNE Sec/Twnshp/Rge: 11-18S-15W
1665 feet from N Section Line, 1570 feet from E Section Line
Lease Name: MANETH Well #: 1
County: BARTON Total Vertical Depth: 3622 feet

Operator License No.: 5259 String Size Depth (ft) Pulled (ft) Comments
Op Name: MAI OIL OPERATIONS, INC. PROD 5.5 3622 2024 175 SX
Address: 8411 PRESTON RD STE 800 SURF 8.625 435 225 SX
DALLAS, TX 75225

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/09/2018 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BRENT HOMEIER Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 445-2353

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Cut casing at 2024' leaving 1598' of casing in hole.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2018 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Sanded bottom perforation off and spotted with 5 sx cement on top. Cut casing at 2024'. Pulled casing to 1600' and pumped 125 sx cement w/200 # hulls. Pulled casing to 1025' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300' and pumped 80 sx cement. Circulated cement. POOH. Cellar stayed full.

GPS: 38.50246 -098.94645

Perfs:

Top	Bot	Thru	Comments
3569	3575		
3474	3478		
3456	3460		
3373	3376		
3363	3367		
3326	3330		
3313	3317		

INVOICED


JUL 17 2018

Remarks: QUALITY CEMENTING TICKET # 763

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

MAY 31 2018

RECEIVED

MAY 16 2018