

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25544-00-00
Spot: SESWNWSE Sec/Twnshp/Rge: 2-18S-15W
1375 feet from S Section Line, 2050 feet from E Section Line
Lease Name: BARTONEK Well #: 1
County: BARTON Total Vertical Depth: 3612 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3612	2060	160 SX
SURF	8.625	1021		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/08/2018 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BRENT HOMEIER Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 445-2353

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Cut casing at 2060' leaving 1552' of casing in well.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/08/2018 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Sanded off bottom and spotted with 5 sx cement on top. Cut casing at 2060'. Pulled casing to 1600' and pumped 125 sx cement w/200 # hulls. Pulled casing to 1025' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300' and pumped 80 sx cement. Circulated cement to the pit. POOH. Cellar stayed full.

GPS: 38.51081 -098.94803

Perfs:

Top	Bot	Thru	Comments
3568	3574		
3466	3470		
3450	3454		
3358	3362		
3308	3312		

INVOICED

JUL 17 2018

Remarks: QUALITY CEMENTING TICKET # 761

Plugged through: CSG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

MAY 16 2018

KCC WICHITA

MAY 31 2018

RECEIVED