

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-017-20925-00-01
Spot: SESESENW Sec/Twnshp/Rge: 13-19S-6E
2716 feet from S Section Line, 2709 feet from E Section Line
Lease Name: BARBARA J. WELLS TRUST Well #: 1A
County: CHASE Total Vertical Depth: 1875 feet

Operator License No.: 35490
Op Name: MATTHEWS ENERGY, LLC
Address: PO BOX 2128
TRAVERSE CITY, MI 49685

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1788		
PROD	5.5	1876		225 SX
SURF	8.625	220		125 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/26/2018 12:00 AM
Plug Co. License No.: 30141 Plug Co. Name: SUMMIT DRILLING COMPANY
Proposal Rcvd. from: SHANE MILLER Company: MATTHEWS ENERGY, LLC Phone: (231) 534-5415

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/26/2018 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

- 1) CIBP set at 1788'
- 2) Ran in tubing to approx 1780. Spotted 50 sks 60/40/4% w/ 2% CaCl
- 3) Pulled tubing up to 275', ran in wireline and tagged top of plug at 1389'
- 4) Loaded hole with water, pressure tested bottom plug at 300 psi -- passed
- 5) Pumped 31 sks 60/40/4% cement at 275', circulated cement to surface. Pulled tubing out and topped off well with cement. (Backside cement was circulated to surface when well was completed)

Perfs:

Top	Bot	Thru	Comments
1803	1806		
1780	1783		

INVOICED

JUL 17 2018

Remarks: CEMENTING COMPLETED BY QES, EL DORADO, KS. TICKET #: 54841

Plugged through: TBG

District: 02

Signed [Signature] 411
(TECHNICIAN)

✓