

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-02190-00-00
Spot: SENWNWSW Sec/Twnshp/Rgc: 11-24S-18E
2152 feet from S Section Line, 4747 feet from E Section Line
Lease Name: HOWLAND A Well #: 2K
County: ALLEN Total Vertical Depth: 800 feet

Operator License No.: 33783
Op Name: MICHAEL DRILLING LLC
Address: 1304 E ST PO BOX 402
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD 2		800		30 SX
PROD 2		880		
SURF 7		20		5 SX
SURF 7		40		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2018 12:00 AM
Plug Co. License No.: 33783 Plug Co. Name: MICHAEL DRILLING LLC
Proposal Revd. from: RICK MICHAEL Company: _____ Phone: (620) 496-7795

Proposed Plugging Method: Run 1" to l.d. fill with cement , run down outside fill to surface

Plugging Proposal Received By: RYAN DULING Witness Type: NONE
Date/Time Plugging Completed: 03/20/2018 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe inside the 2" casing to TD. Ran 1" pipe down the backside of the 2" casing to 500'. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled 1" pipe out of the 2" casing. Pumped and circulated cement through the 1" pipe on the backside of the 2" casing from 500' to surface. Pulled the 1" pipe out of the well. Topped the well off with cement. A total of 84 sacks of portland cement was reported used to plug this well.

RECEIVED
KCC DIST # 3
JUN 20 2018
CHANUTE, KS

RD

INVOICED
JUL 17 2018

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)