

6 061306

8-18-87

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009.07204.0000

SE, SEC. 12, T 20 S, R 12 W/E

1980 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Schartz C Well # 5

Operator: Kaiser Francis Oil Co.

County Barton 108.71

Name & Address Box 21468

Well Total Depth 3345 feet

Tulsa, Ok. 74121-1468

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 337

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Great Bend, Kansas 67530

Company to plug at: Hour: 11:00 AM Day: 18 Month: August Year: 19 87

Plugging proposal received from Glenn Jackson

(company name) Kaiser Francis Oil Co. (phone) 316-564-3214

were: Order 200 sks 65/35 Pozmix 10% Gel 2% Econolite, 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:00 PM Day: 18 Month: August Year: 19 87

ACTUAL PLUGGING REPORT 8 5/8" set at 337' w/170 sks. 5 1/2" set at 3337' w/100 sks.

Open hole 8'. Pumped in 5 1/2". 5 sks Hulls, 150 sks cement w/200 Psi. Pumped in 8 5/8"

50 sks cement w/450 Psi. Shot holes at 620' in Anhy.

STATE CORPORATION COMMISSION

9-1-87 SEP 1 1987

Remarks: By B. J. Titan

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this form.)

INVOICED ~~VOIDED~~ observe this plugging.

DATE 9-3-87

Signed Gilbert G. Scheck
(TECHNICIAN)
Gilbert G. Scheck

INV. NO. 17996

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1967

CONSERVATION DIVISION
Wichita, Kansas

7-man... with...

C. E. ASH et al
Schartz "C" # 5
CW $\frac{1}{2}$ NE SE Sec. 12-20-12W
Barton County, Kansas

Comm. Rig Up :	7-14-1948	Elevation :	1787 (Card)
Comm. Drilling:	9-1-1948	Initial Prod.:	300 bbl.
Comp. Rotary :	9-14-1948	Contractor :	C. E. Ash
Completed :	9-20-1948	Tools :	Rotary

CASING RECORD
Pulled

<u>Run</u>				<u>Left In</u>
337'	8 5/8"	(Cem. w/170 sax)	337'	8 5/8"
3337'	5 1/2"	(Cem. w/100 sax)	3337'	5 1/2"

STRATA DEPTH

Sand	100
Red bed	280
Shale blue	300
Red bed	565
Anhydrite lime	615
Shale & shells	1060
Salt	1200
Shale & shells	1430
Lime	1500
Shale	1700
Lime	1800
Shale & lime shells	1950
Lime	2055
Shale	2385
Lime & shale	2555
Lime	2630
Lime & shale	2745
Lime	2875
Lime & shale	2905
Lime	2960
Lime & shale	3110
Lime	3345
Total Depth	3345

TOPS: R. B.

Brown lime	3073'
KC or White lime	3094'
Base /KC lime	3330
Conglomerate	none
Arbuckle lime	3335 (-1548)

*3094
1787
-1307*

When hole was cleaned out to bottom of Rotary hole of 3341' (-1154) the hole filled 2550' with oil and no water in 12 hrs.

Showed more oil 3341'-3343' (-1554-56)
Probably more oil 3343'-3345' (-1556-58) TD
Swabbed 13 bbls. oil per hr. for 3 hrs. no water.
Est. 300 bbls. per day.

*10' arb. penetrated
prod 8' open hole.*

15.069.07204.0000

WELL PLUGGING RECORD CARD

INVOICE NO. _____

OPERATOR Francis Oil & Gas, Inc.

ADDRESS 905 PALACE Bldg. Tulsa, Oklahoma 74103

SEND INVOICE TO SAME

ADDRESS _____

LEASE NAME SCHARTZ "C" WELL NO. 5

WELL LOCATION CW/2 NE SE SEC. 12 TWP. 20 RGE. 12W COUNTY Broken

APP'L REC'D 3/29/69 PERMISSION DATE 3/29/69 LOG REC'D ✓ T.D. 3345'

WELL CLASS: OIL ✓ GAS _____ DISPOSAL _____ INPUT _____ D&A _____ OTHER _____

AGENT TEWAN D.A. REPORT REC'D _____ AFFID REC'D _____ DATE PLUGGED _____

AMOUNT FEE _____ INVOICE DATE _____ AMOUNT PAID _____ DATE PAID _____

DATE OVERDUE _____ NOTICES SENT _____

Send copy of letter to Don Tewan to void authority