

5-4

15-009-23374.0000/07

4-062633

R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-23,374
SW SW /4 SEC. 24, 20 S, 11 W
660 feet from S section line
780 feet from E section line

Operator license# 5030 Lease Sessler well # 1

Operator: Vess Oil Corporation County Barton

Address: 8100 E. 22nd Street Well total depth 3252 feet ^{105.69}
N. Building #300 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67226 Surface pipe 8 5/8 Inch @ 452 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Box 347, Chase, Kansas 67524

Company to plug at: Hour: 10:00A.M Day: 4 Month: May Year: 92

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pulling, Inc. Phone: 316-938-2943

Were: Order 250 sks. of 60/40 posmix - 8% gel. - 5 sks. hulls.

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 8:00P.M., Day: 4, Month: May, Year: 92

Actual plugging report: 8 5/8" @ 452' w/310 sks. 5 1/2" @ 3251' w/150
sk. Top perf. @ 3120'. Plugged bottom with sand and 5 sks. cement to
3078'. Shot pipe one time and recovered 1700'. Pump in 8 5/8" 25 sks.
cement followed with 5 sks. hulls in 225 sks. cement w/800 P.S.I.
Max. pressure on 8 5/8" - 800 P.S.I. Shut in @ 600 P.S.I.
Total sacks 250 cement.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES 452 NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 1749 GL

I did X / did not observe the plugging. Gilbert G. Scheck

DATE 5-22-92

(agent)

INV. NO. 35324