

To: 6 031198
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

1937

SE NE NW, SEC. 24, T. 20 S, R. 11 W/E

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5214

Lease Name Herman Peterwell # 5

Operator: Lario Oil and Gas Co.

County Barton 121.71

Name & Address 301 S. Market

Well Total Depth 3745 feet

Wichita, Ks. 67202

Conductor Pipe: Size 12 1/2 feet 153

Surface Casing: Size 8 1/4 feet 3254

Abandoned Oil Well Gas Well RECEIVED SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Great Bend, Ks. 1-18-89

Company to plug at: Hour: PM Day: Month: Dec Year: 19 88

Plugging proposal received from E.G. Kasselmann

(company name) Lario (phone)

were: 12 1/2" set at 153' w/140 sks. 8 1/2" set at 3254' w/150 sks. 5 1/2" set at 3409'. 200 sks. O.H. 3409' - 3745'. Fiberglass was milled to 1650' where progress ended. 5 1/2" casing was loose and pulled from 520'. Order 400 sks 60/40 Poz 8% Gel w/F.C. and Hulls Halliburton Cement Co. Perf 8 5/8" at 200'.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:33PM Day: 3 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Ran tubing to 1650'. Circulated to surface. Tied onto 12 1/2" and 8 1/4" and squeezed w/total 400 sks cement w/5 sks of Hulls mixed into max psi 400#. Close in psi 200#. Plug completed.

Remarks: (If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

FORM CP-2/3 Rev. 01-84

INVOICED
DATE 1-19-89
INV. NO. 23713