

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-26124-00-00
Spot: SENWSW Sec/Twnshp/Rge: 8-34S-11E
1759 feet from S Section Line, 4399 feet from E Section Line
Lease Name: SPUR Well #: 31
County: CHAUTAUQUA Total Vertical Depth: 1465 feet

Operator License No.: 5970
Op Name: ELMORE, JOHN A. OR PATRICIA R.
Address: 776 HWY 99
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1465		129 SX
SURF	7	40		9 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2018 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: _____ Phone: (620) 249-2519

Proposed Plugging Method: According to KCC Rules and Regulations.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 06/25/2018 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1400' gelled hole and spotted 5 sack plug. Pulled up to 800' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 45 sacks of cement with 3% gell was used to plug this well.

RECEIVED
KCC DIST # 3
JUN 26 2018
CHANUTE, KS

DS

INVOICED


JUL 16 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)