

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-30166-00-01  
Spot: NWNWSESE Sec/Twnshp/Rge: 4-15S-13W  
1042 feet from S Section Line, 1077 feet from E Section Line  
Lease Name: LETSCH WFS Well #: 7  
County: RUSSELL Total Vertical Depth: 3100 feet

Operator License No.: 34506  
Op Name: EMPIRE ENERGY E&P, LLC  
Address: 345 RIVERVIEW ST., STE 540  
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3100		250 SX
SURF	8.625	780		450 SX

Well Type: EOR UIC Docket No: E07589.2 Date/Time to Plug: 05/10/2018 10:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: RICHARD LACEY Company: EMPIRE ENERGY E&P, LLC DBA Phone: (620) 617-0603

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/10/2018 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 400' and 800'. Ran tubing to 2968' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1750' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 850' and pumped 85 sx cement. Circulated cement out of the backside. Closed valve and pumped an additional 95 sx cement. Circulated cement out of the braden head. POOH. Filled casing with 15 sx cement. Circulated cement out of the braden head.

GPS: 38.77218 -098.76587

Perfs:

Top	Bot	Thru	Comments
3036	3038		
3029	3032		
3019	3023		

INVOICED  
JUL 16 2018

Remarks: COPELAND ACID AND CEMENTING SERVICES TICKET # 45840.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

MAY 16 2018

KCC WICHITA

MAY 31 2018

RECEIVED

Form CP-2/3