

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26535-00-00
Spot: SWSENWNW Sec/Twnshp/Rge: 21-13S-20W
1310 feet from N Section Line, 705 feet from W Section Line
Lease Name: SCHUMACHER Well #: 2
County: ELLIS Total Vertical Depth: 3930 feet

Operator License No.: 6509
Op Name: CLARK, JIM D. DBA CLA-MAR OIL, CO
Address: PO BOX 506
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3911		180 SX
SURF	8.625	222		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/25/2018 11:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Revd. from: JASON B CLARK Company: CLARK, JIM D. DBA CLA-MAR OIL, Phone: (785) 259-5575

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls and 10 sx gel.
Production perforations: 3818' - 3824', 1577' w/150 sx cement.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/25/2018 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3720' and pumped 10 sx gel followed by 70 sx cement w/300 # hulls. Pulled tubing to 2050' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1025' and pumped 115 sx cement to circulate cement to surface. Hooked to 8 5/8" x 5 1/2" annulus and pressured to 300 # immediately. Topped off 5 1/2" casing with 15 sx cement.

GPS: 38.91017N -099.55582W

Perfs:

Top	Bot	Thru	Comments
3818	3824		

Remarks: SWIFT SERVICES TICKET # 27275

Plugged through: TBG

INVOICED

JUL 16 2018

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

MAY 29 2018

JUN 25 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3