

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-21205-00-01  
Spot: N2N2SWSW Sec/Twnshp/Rge: 21-13S-20W  
1060 feet from S Section Line, 660 feet from W Section Line  
Lease Name: SCHUMACHER TRUST Well #: 1  
County: ELLIS Total Vertical Depth: 3853 feet

Operator License No.: 6509  
Op Name: CLARK, JIM D. DBA CLA-MAR OIL, CO  
Address: PO BOX 506  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3845		150 SX
SURF	8.625	222		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2018 2:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JASON B CLARK Company: CLARK, JIM D. DBA CLA-MAR OIL, Phone: (785) 259-5575

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls and 10 sx gel spacer.  
1580' w/350 sx cement.  
Production perforations: 3851' - 3853'.  
Casing leak: 2700' - 2705'.

Plugging Proposal Received By: PAT STAAB  
Date/Time Plugging Completed: 05/25/2018 5:00 PM

WitnessType: COMPLETE (100%) - Not witnessed  
KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3750' and pumped 10 sx gel followed by 70 sx cement w/300 # hulls. Pulled tubing to 2050' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1025' and pumped 115 sx cement to circulate cement to surface. Visually checked 8 5/8" x 5 1/2" annulus and cement was to surface. Topped off 5 1/2" casing with 15 sx cement.

GPS: 38.90216N -099.55573W

Perfs:

Top	Bot	Thru	Comments
3851	3853		

Remarks: SWIFT SERVICES TICKET # 27276

Plugged through: TBG

INVOICED

JUL 16 2018

District: 04

Signed \_\_\_\_\_

Pat Bedore

Received  
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

MAY 29 2018

JUN 12 2018

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS