

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-01867-00-02
Spot: S2SESE Sec/Twnshp/Rge: 9-34S-8E
330 feet from S Section Line, 963 feet from E Section Line
Lease Name: MCEWEN Well #: 1
County: COWLEY Total Vertical Depth: 2155 feet

Operator License No.: 33809
Op Name: BELPORT OIL, INC.
Address: 10830 E 45TH ST STE 206
TULSA, OK 74146

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	2.875	1930		
PKR		1925		
PROD	4.5	2126		75 SX
SURF	7	44		25 SX
T1	1	1925		

Well Type: EOR UIC Docket No: E18164.2 Date/Time to Plug: 05/24/2018 1:00 PM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: FRED MCADAM Company: Phone: (620) 330-7661

Proposed Plugging Method: AS PER KCC RULES & REGS / CEMENT 2 7/8" TUBING TOP TO BOTTOM

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 05/29/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH WITH 1" TUBING @ 1950', ELMORES ESTABLISHED CIRCULATION, MIXED & PUMPED 100 SXS CLASS A COMMON. CEMENT DID NOT CIRCULATE. 5-29-2018, TAGGED CEMENT @ 900'. RIH W/TUBING @ 900', ELMORES ESTABLISHED CIRCULATION, MIXED & PUMPED 25 SXS CLASS A CEMENT TO SURFACE. LAYED DOWN 1" TUBING, RIH WITH 1" TUBING ON BACKSIDE @ 125', ELMORES MIXED & PUMPED 20 SXS TO SURFACE. CEMENT CIRCUALTED. TICKET #13514.

Perfs:

Top	Bot	Thru	Comments
2100	2110	CSG	
2040	2060	CSG	
1940	1952	CSG	

INVOICED
JUL 16 2018

Remarks: FAILED MIT

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)