

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-22495-00-00
Spot: NWNESENE Sec/Twnshp/Rge: 9-34S-8E
3665 feet from S Section Line, 492 feet from E Section Line
Lease Name: ZIMMERMAN R Well #: 1
County: COWLEY Total Vertical Depth: 2464 feet

Operator License No.: 33809

Op Name: BELPORT OIL, INC.

Address: 10830 E 45TH ST STE 206
TULSA, OK 74146

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2483		0 SX
SURF	8.625	122		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/28/2018 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Revd. from: FRED MCADAM

Company:

Phone: (620) 330-7661

Proposed
Plugging
Method:

AS PER KCC RULE & REGS. CEMENT @ 2350', PERFORATE AND CIRCULATE AT 500'.

Plugging Proposal Received By: JEFF KLOCK

Witness Type: PARTIAL

Date/Time Plugging Completed: 05/24/2018 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH WITH TUBING @ 2410', ELMORES MIXED & PUMPED 1 SX GEL & 4 BBLs
WATER & 10 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED @ 2040'.
LOADED HOLE & PRESSURED CASING. HELD OK. RIH ON WIRELINE
PERFORATED SQUEEZE HOLES @ 550'. RIH WITH TUBING @ 550', ELMORES
ESTABLISHED CIRCULATION, MIXED & PUMPED 3 15 SXS CLASS A COMMON TO
SURFACE. CEMENT CIRCULATED. CEMENT TICKET #13513.

Top	Bot	Thru	Comments
2404	2412	CSG	

INVOICED

JUL 16 2018

Remarks: DENIED TA / LENGTH OF TIME

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

1/5