

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21464-00-00
Spot: N2NWSENE Sec/Twnshp/Rge: 22-14S-29W
3658 feet from S Section Line, 990 feet from E Section Line
Lease Name: PRATHER Well #: 1
County: GOVE Total Vertical Depth: 4450 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4362		210 SX
SURF	8.625	275		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2018 10:00 AM
Plug Co. License No.: 99975 Plug Co. Name: COMPANY SERVICING TOOLS
Proposal Rcvd. from: RENE Company: FALCON EXPLORATION, INC. DBA Phone: (785) 483-1559

Proposed Plugging Method: Ordered 410 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Production perforations: 3884' - 4217'.
Tubing stuck in hole at 3508'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2018 3:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3446' and pumped 70 sx cement. Pulled tubing to 2408' and pumped 70 sx cement w/200 # hulls. Pulled tubing to 1350' and pumped 160 sx cement w/100 # hulls. Pulled tubing to 920' and pumped 110 sx cement to circulate cement to surface. Pulled tubing. Topped off 4 1/2" casing with 70 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 15 sx cement. Shut in pressure 200 psi.

GPS: 38.82519N -100.52420W

Perfs:

Top	Bot	Thru	Comments
4212	4217		
4188	4190		
4139	4141		
3884	3948		

INVOICED

JUL 17 2018

Remarks: GLOBAL CEMENTING TICKET # 3340

Plugged through: TBG

District: 04

Received Signed
KANSAS CORPORATION COMMISSION

Pat Bedore
(TECHNICIAN)

CM

MAY 29 2018

JUN 25 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3