

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-26623-00-00
Spot: SWSWSWSW Sec/Twnshp/Rge: 22-34S-11E
278 feet from S Section Line, 5017 feet from E Section Line
Lease Name: WHITE Well #: 33
County: CHAUTAUQUA Total Vertical Depth: 1320 feet

Operator License No.: 34707
Op Name: FARRIS OIL, INC.
Address: 888 STATE HWY 99
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1320		160 SX
SURF	8	40		12 SX
T1	2.375	1300		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Revd. from: DEE FARRIS Company: _____ Phone: (620) 725-3772

Proposed Plugging Method: Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 06/13/2018 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1260' gelled hole and spotted 5 sack plug. Pulled up to 1050' and spotted 5 sack plug. Pulled 1" and perforated casing at 650' and 350'. Ran 1" back into 650' and spotted 10 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 115 sacks of cement with 3% gell was used to plug this well. Well was cut off and locaiton restored.

Perfs:

Top	Bot	Thru	Comments
1280	1300		
1056	1066		

RECEIVED
KCC DIST #3
JUN 26 2018
CHANUTE, KS

INVOICED
JUL 17 2018

DS

Remarks:

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)