

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-03036-00-00
Spot: NESWNE Sec/Twnshp/Rge: 6-35S-15E
3636 feet from S Section Line, 1372 feet from E Section Line
Lease Name: MCDANIELS Well #: OW-1
County: MONTGOMERY Total Vertical Depth: 535 feet

Operator License No.: 34930
Op Name: FREDDY VAN'S CONSTRUCTION, INC.
Address: 2513 E 4TH
PITTSBURG, KS 66762

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD		0		0 SX
SURF	7	20		0 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/05/2018 12:00 AM
Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: RON CUNNINGHAM Company: Phone: (620) 289-4700

Proposed Plugging Method: Run 2" to bottom, wash down, get hole, put a 50' plug on bottom, pull up to 225', cement to surface, pull tubing out, top off cement, cut off well head, restore location.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 06/05/2018 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 535', tried to wash and drill down well, but couldn't. Gelled hole and spotted 10 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 45 sacks of cement were used to plug this well.

RECEIVED
KCC DIST #3
JUN 12 2018
CHANUTE, KS

DS

INVOICED
JUL 17 2018

Remarks: PLUGGED BECAUSE THE WELL WAS A SURFACE CASING ONLY WELL.

Plugged through: TBG

District: 03

Signed

Duane A. Sims

(TECHNICIAN)