

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-22620-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 4-17S-15W  
4950 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: SEIDL Well #: 1  
County: BARTON Total Vertical Depth: 3670 feet

Operator License No.: 32528 String Size Depth (ft) Pulled (ft) Comments  
Op Name: FUNK OIL & OPERATING, LLC PROD 8.625 1132 425 SX  
Address: 127 EVES DR SURF 4.5 3619 2435 175 SX  
RUSSELL, KS 67665

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/30/2018 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: DAVE FUNK Company: FUNK OIL & OPERATING, LLC DB Phone: (785) 445-8182

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/700 # hulls.  
Cut 5 1/2" casing at 2435' leaving 1184' in hole.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/30/2018 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Sanded off bottom perforation and spotted 5 sx of cement on top. Cut casing at 2435'. Pulled casing to 1600' and pumped 125 sx cement w/400 # hulls. Pulled casing to 1135' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300' and pumped 85 sx cement. Circulated cement to the cellar and pit. POOH. Cellar stayed full.

GPS: 38.60828 -098.99101

INVOICED  
JUL 17 2018

Remarks: QUALITY CEMENTING TICKET # 755

Plugged through: CSG

District: 04

Signed

*Ray Dinkel*

(TECHNICIAN)

CM

KCC WICHITA

MAY 17 2018

RECEIVED

MAY 03 2018