

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-24560-00-00  
Spot: SWNE Sec/Twnshp/Rge: 16-35S-4E  
4117 feet from S Section Line, 1033 feet from E Section Line  
Lease Name: GREY GOOSE Well #: 1  
County: COWLEY Total Vertical Depth: 3815 feet

Operator License No.: 34950  
Op Name: FUTURE ACQUISITION COMPANY LLC  
Address: PO BOX 1129  
FULSHEAR, TX 77441

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3672		
PROD	5.5	3812		265 SX
SURF	8.625	263		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/14/2018 9:00 AM  
Plug Co. License No.: 35553 Plug Co. Name: SOUTH CENTRAL WELL SERVICE LLC  
Proposal Revd. from: AARON FROMAN Company: \_\_\_\_\_ Phone: (316) 993-7272

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/14/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3300', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. CUT CASING @ 1310', LAID CASING DOWN @ 315', QUALITY WELL SERVICE, ESTABLISHED CIRCULATION, MIXED & PUMPED 90 SXS 60/40 POZMIX 4% GEL TO SURFACE. FINISHED LAYING DOWN 5.5 CASING. TOPPED WELL BACK TO SURFACE W/20 SXS. QUALITY CEMENT #6859.

Perfs:

Top	Bot	Thru	Comments
3706	3714	CSG	
3360	3392	CSG	
3348	3354	CSG	
3326	3336	CSG	

INVOICED  
JUL 17 2018

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

JK